INVITATION FOR BID #11PB060

SCOTTSDALE AIRPORT AIRCRAFT PARKING APRON REHABILITATION PHASE 3

JULY 7, 2011

ADDENDUM #3

The following changes/additional information is provided and shall affect this solicitation:

1. <u>BID FORM, SCHEDULE OF BID ITEMS, PAGE 64</u>:

Delete Schedule of Bid Items on page 64 AD1 and replace with the attached Schedule of Bid Items, page 64 AD3.

All other Terms and Conditions remain the same. Acknowledgement of the addendum is required on the Signature Page of your offer.

Karie Ingles, CPPB
Bid & Contract Specialist
Email: kingles@scottsdaleaz.gov

Scottsdale Airport
Rehabilitate Landmark North Apron
11PB060
Schedule of Bid Items

Item No.	Spec. No.	Item	Quantity	Unit	Unit Cost	Total Cost
1	M-101-4.1	Mobilization	1	LS		
2	M-102-2.1	Contractor Quality Control Program	1	LS		
3	M-103-3.1	Utility Relocation	1	FA	$ 25,000.00	$ 25,000.00
4	M-104-4.1.1	Removal of Bituminous Pavement (Depth Varies)	37,486	SY		
5	M-104-4.1.2	Removal of Miscellaneous Improvements	1	LS		
6	M-104-4.1.3	Removal of Tie Down Anchors and Accessories	80	EA		
7	M-105-3.1	Temporary Signage and Traffic Control	1	LS		
8	M-106-4.1	Pre-Emergent Herbacide	1967	SY		
9	M-107-4.1	Tie-Down Anchors with Accessories	24	EA		
10	P-152-4.1	Unclassified Excavation	38,716	SY		
11	P-152-4.2	Subgrade Preparation (6")	2,615	SY		
12	P-152-4.3	Removal & Replacement of Unsuitable Material	1	FA	$ 60,000.00	$ 60,000.00
13	P-156-5.1	Temporary Air,Water Pollution and Siltation Control	1	LS		
14	P-209-5.1	Crushed Aggregate Base Course (8")	36,380	SY		
15	P-209-5.2	Crushed Aggregate Base Course (6")	535	SY		
16	P-218-5.1	Crushed Aggregate Slope Protection	1,967	SY		
17	P-301-6.1	Soil Cement Base Course (6")	36,380	SY		
18	P-301-6.2	Portland Cement	900	TON		
19	P-401-8.1	Bituminous Surface Course (2")	4,500	TON		
20	P-403-8.1	Bituminous Base Course (2.5")	5,600	TON		
21	P-602-5.1	Bituminous Curing Seal	18	TON		
22	P-603-5.1	Bituminous Tack Coat	8	TON		
23	P-620-5.1	Apron and Taxiway Painting	4,079	SF		
24	P-620-5.2	Reflective Media	400	LB		
25	P-620-5.3	Pavement Marking Removal	120	SF		
26	D-705-5.1	4" HDPE Perforated Pipe	923	LF		
27	SP	Construction Layout Staking	1	LS		
28		Concrete Valley Gutter (9')	113	LF		
29		Ribbon Curb (2')	21	LF		
30	MAG 321	Asphalt Concrete Pavement Replacement	400	SY		
31	L-108-5.1	Trench and Backfill	350	LF		
32	L-108-5.2	L-824 #8 5 KV Conductor	1000	LF		
33	L-108-5.3	Ground Conductor	1000	LF		
34	L-110-5.1	2" PVC Duct	250	LF		
35	L-110-5.2	2 - 4" Concrete Encased Duct	90	LF		
36	L-115-5.1	Electrical Pullbox (12" x 18")	3	EA		
37	I-125-5.1	Salvaged Taxiway Edgelight With New L-867 Base	9	EA		
38	L-125-5.2	New L858 Size 1 - 2 Module Sign	1	EA		

Bid Total $ _____

Bid Amount is: _____ **Dollars**

And _____ **Cents**

Name of Firm: _____

Signature: _____